Community Center Renovation Proposal

Version 2 - prepared for the board of trustees

1. Summary

This proposal describes the renovation of the Harbor View Community Center, a two-storey building from 1978 used by local clubs, a day nursery and an evening language school. The proposal covers the roof, the heating system and step-free access to the main hall. Work is planned in three phases so that the building stays open during most of the renovation.

2. Survey results

Since the first draft, the facilities team has completed a structural survey of the roof deck. The deck itself is sound, which removes the need for the timber repairs listed as optional in the first draft. The survey report is attached as an appendix to this version.

The survey also measured the heat loss of the building envelope. Most of the loss comes from the roof and from the single glazing on the north side, which confirms the priorities of this proposal. No asbestos was found in the areas affected by the works. The survey team recommends a second inspection of the roof deck ten years after the new membrane is laid, and a yearly check of the gutters and of the roof drains, which were partly blocked on the day of the visit. The full list of measurements is part of the appendix, together with photos of each roof section.

3. Current condition

The building is safe and in daily use, but three elements have reached the end of their service life. Repairs have become more frequent and more expensive every year, and the boiler is 27 years old. The main points raised by the last inspection are listed below.

- Roof: the flat roof membrane leaks above the main hall after heavy rain.
- Heating: the gas boiler fails several times each winter.
- Access: the main hall can only be reached by a flight of six steps.
- Windows: single glazing on the north side causes heat loss.
- Drainage: the roof drains and gutters are partly blocked.
- Lighting: the hall lighting uses old fluorescent tubes.

4. Proposed works

The committee strongly recommends replacing the roof membrane and adding 140 mm of insulation. The gas boiler is replaced by two air-source heat pumps with a smaller gas unit kept as backup for very cold days. A ramp and an automatic door give step-free access to the main hall. The single glazing on the north side is replaced by double glazing in the same frames.

5. Budget

The estimate below is based on two quotes per work package. Prices include labour and materials and exclude tax.

Roof membrane and insulation	$48,500
Heat pumps and backup unit	$39,400
Ramp and automatic door	$14,800
North side double glazing	$9,600
Contingency (5%)	$5,615
Total	**$117,915**

A grant from the regional energy fund could cover up to 30% of the heat pump cost. The application must be filed before the end of March.

6. Risks

Delivery times for heat pumps vary between eight and sixteen weeks, so the order has to be placed as soon as the budget is approved. Roof work depends on dry weather. If the summer is wet, phase one moves to the autumn and phase two follows it. The contractor has confirmed that both phases can run in parallel if needed.

7. Schedule

Phase one replaces the roof during the summer break, when the nursery is closed. Phase two installs the heat pumps in September and October. Phase three builds the ramp and replaces the windows. The last phase should end in June 2027, and the hall stays closed for four weeks in total.

8. Decision requested

The board is asked to approve the budget of the three phases, to authorise the grant application, and to appoint a project lead from the facilities team. A progress report will be presented at every board meeting until the work is complete.